



Beach Walker Villas Amelia Island, Florida



Window and Door Specification Manual

June 17, 2020

**BEACH WALKER VILLAS CONDOMINIUM ASSOCIATION
DOOR AND WINDOW SPECIFICATION MANUAL
INDEX PAGE**

Specifications Index

Specification Section 080000 – Sliding Door Replacement
Specification Section 081000 – Exterior Swing Door Replacement
Specification Section 085313 – Window Replacement

Drawing Index

2A-1 – Replacement Window Sill
2A-2 – Replacement Window Sill at Low Roof
2B – Replacement Window Jamb
2C – Replacement Window Head
4A-1 – Replacement Sliding Glass Door or Swing Door Sill W/O tile
4A-2 – Replacement Sliding Glass Door or Swing Door Sill W/ tile
4B – Replacement Sliding Glass Door or Swing Door Jamb
4C – Replacement Sliding Glass Door or Swing Door Head
5 – Sill Pan Isometric Detail

SECTION 080000 – SLIDING DOOR REPLACEMENT

PART 1 – GENERAL

1.1 Scope of Work:

- A. Removal of existing doors and associated exterior and interior trim where required.
- B. Removal of existing exterior stucco and interior drywall as required.
- C. Replacement of existing doors including installation of all flashing, waterproofing, stucco, accessories, and caulk/sealants as required to produce a complete watertight installation.
- D. Removal and replacement of deteriorated wall framing, exterior sheathing and wall insulation when encountered at door rough openings.

1.2 Permits, Fees and Insurance:

- A. The Owner and/or their contractor shall coordinate all approvals through the Association Board and the Architectural Review Board.
- B. Contractor shall secure all necessary permits prior to commencement of the work.
- C. Contractor shall procure and maintain in force until the completion of work the following insurances in the amounts required by the Owner and the Association Board: general liability insurance, employer's liability insurance, automobile insurance and worker compensation. Contractor shall insure that current insurance certificates are on file with the appropriate management firm and/or association representative.

1.3 Quality Assurance:

- A. Comply with governing codes and regulations. Provide products of acceptable manufacturers, approved by the local building code agency and have been in satisfactory use in similar service for three years. Use experienced installers.
- B. It is the responsibility of the Contractor to ensure that the replacement door units design wind pressures, at the time of procurement and installation, comply with the current Florida Building Code. CONTRACTOR SHALL CONTACT ENGINEER TO VERIFY COMPLIANCE.
- C. Manufacturer's Qualifications: Company specializing in the manufacture of products for a minimum of 5 years. Company shall be a member of the American Architectural Manufacturers Association (AAMA).

- D. Installer Qualifications: Company specializing in the performance of the work for a minimum of 5 years.
- E. All work shall be performed in accordance with the manufacturer's recommended installation instructions and details.
- F. Contractor may substitute other equivalent products as approved by the Owner, Association Board and Architectural Review Board if required.
- G. All temporary utility services, including toilet facilities, are to be obtained and paid for by the contractors performing the work described herein.

1.4 Warranty

- A. Manufacture: Provide manufacturer's standard warranty.
- B. Installer: Provide all labor and materials required to repair work that fails to perform for (5) five years following the date of substantial completion.

1.5 System Performance Requirements:

- A. General: Provide door units that comply with performance requirements specified, as demonstrated by testing the manufacturer's corresponding stock systems. Test each type and size of required unit through a recognized independent testing laboratory or agency using the tests & test procedures specified below, and in accordance with procedures specified in AAMA 101, including requirements of AAMA 101, Section 3, "Optional Performance Classes." All assemblies shall be in accordance with the current Building Code.
- B. Design Wind Pressure Requirements: -70/+70 psf.
- C. Uniform Load Structural and Deflection Tests: Test in accordance with ASTM E 330 at 150 percent of the design pressure. After each specified loading, there shall be no glass breakage, permanent damage to fasteners, hardware parts, support arms or actuating mechanisms or any other damage, which causes the window to be inoperable. No member shall deflect more than 1/175 of its span under load, and there shall be no permanent deformation of any main frame, sash, pane, or ventilator member in excess of 0.2 percent of its span.
- D. Water Penetration (Laboratory): Test in accordance with ASTM E 331, and ASTM E 547 both at 15% of the structural design pressure rating. There shall be no water penetration as defined in the test method.
- E. Impact Resistance: Provide window units and glazing that have been tested to pass the large and small missile impact test per ASTM E 1886. Obtain approval from the Owner if impact glass is not intended to be used.

- F. Water Penetration (Field) Test in accordance with ASTM E 1105 at 15% of the structural design pressure rating. There shall be no water penetration as defined in the test method. The AMMA permitted 2/3 reduction in passing criteria for testing of field installations shall NOT be allowed.
- G. Air infiltration: Test in accordance with ASTM E 283 at 1.6 lbf/ft². Air infiltration rate shall not exceed 0.03 cfm/ft².
- H. Forced-Entry Resistance: Provide units that comply with requirements for Performance Level 10 when tested in accordance with AAMA 1302.5-76 Test A through G.
- I. Condensation Resistance Factor (CRF): Provide units with CRF of 16 per AAMA 1503.
- J. Energy Performance: Provide units with a maximum thermal transmittance (u-value) of 0.40 (or as required to achieve an Energy Star rating) when tested in accordance with AAMA 1503.1, latest edition.
- K. Light emission: Provide units that comply with Florida Statute 62B-55 or other local ordinance requirements for light emission for the protection of sea turtle nesting.
- L. Solar Heat Gain Coefficient (SHGC): Provide units with SHGC <0.25. Manufacturer: Provide manufacturer's standard warranty.

1.6 Work Performance Field Verification:

- A. Watertight performance of all work is required.
- B. All newly installed window and sliding glass door installations must pass a visual inspection, operation test, an AAMA 501.2 hose test, where deemed appropriate, and an AAMA 502 sill dam test following completed installation and prior to the installation of interior trim components.
- C. Door installations that fail the AAMA 501.2 hose test and AAMA 502 sill dam test will not be approved for payment until passing results are achieved. If passing results cannot be achieved, the unit shall be replaced with one that does pass at no additional cost to the owner.

PART 2 - SUBMITTALS

2.1 General:

- A. Contractor shall submit proof of employer's liability insurance, general liability insurance, automobile insurance and workman's compensation.
- B. Contractor shall submit names and addresses for all suppliers and all subcontractors providing materials and/or labor on project.

- C. For substitutions, Contractor shall submit proof data to demonstrate that substitutions are equal in performance and durability to materials specified.
- D. Contractor shall submit 4 copies of all requested submittal materials to the Association Board for approval prior to commencement of the work. Contractor shall indicate Owner's approval on submittal cover sheet.

2.2 Door Units:

- A. Product Data: Contractor shall submit manufacturer's product literature for all products and accessories furnished.
- B. Florida Building Code approval and/or Miami-Dade Notice of Acceptance "NOA" indicating the specific model/series product's compliance with code requirements.
- C. Design Pressure Calculation for each window or door opening to be modified.
- D. Installation Instructions: Contractor shall submit manufacturer's installation instruction sheets for all products and accessories furnished.
- E. Contract Closeout Submittals: Contractor shall submit to the owner bound manual clearly identified with project name, location and completion date. Identify type and size of new window and sliding glass door units installed. Provide recommendations for periodic inspections, care and maintenance.

2.3 Contractor shall provide manufacturer's product literature, installation instructions and color samples (exposed materials only) for the following:

- A. Waterproofing membrane (liquid applied)
- B. Self-adhered membrane
- C. Joint sealant & backing materials
- D. Elastomeric coating materials

PART 3 - MATERIALS

3.1 Door Units:

- A. Hardware: Stainless steel or approved equivalent corrosion resistant material for the salt air environment.
- B. Color: To match existing.

- C. Sliding Glass Doors: WinDoor 8100 Series or accepted alternate, (equal leg, no fin). Vinyl assemblies may be substituted if they match all technical requirements contained herein and match existing window profile.

3.2 Sill Flashing:

A. Sill Flashing:

1. Type:
 - a. AISI type 316 stainless steel complying with ASTM A-167, with 2D annealed finish. Minimum thickness to be 0.0156" (28 gauge) U.O.N. (see drawings for profile). All corner joints shall be welded.
 - b. PVC manufactured by Jamsill Guard or approved equivalent, size to fit new appurtenance and opening.
2. Dimensions:
 - a. Vertical: Back and end legs compliant with height requirements of Table A3.1 of ASTM E 2112.
 - b. Horizontal: width of pan shall fit the full width of the rough opening so that the base of the vertical perimeter sealant joints are captured within the pan.
 - c. Lateral: Sill pan tray and end dams shall project beyond the exterior plane of the window frame or door frame. The leading horizontal edge of the tray shall contain a down turned leg of a minimum of 3/8-inch.
 - d. End Dam Terminations: Shall project beyond the jamb's perimeter sealant joint. Where exposed to the exterior, the pan legs shall be hemmed and curve cut.
3. Slope: the pan shall be sloped a minimum of 1/8":6" toward the exterior by means necessary.
4. Joints: Fully fused by soldering, welding, or PVC liquid cement. Caulk shall not be used to seal PVC pan overlaps PVC liquid cement must be used.
5. Sealing:
 - a. Installation: Pan shall be set in (3) parallel generously applied continuous beads of sealant along its length and at the corners of the rough opening.
 - b. Interior: The top legs (back and ends) of the sill pan shall be continuously sealed to the sliding glass doorframe to prevent passage of air from outside to inside.
 - c. Exterior: The underside of the pan and the outside surface of the end dams shall be sealed to the wall.
6. Flashing material: Prosoco R-Guard FastFlash or approved equivalent.

3.3 In-Organic Curb (Below Sliding Glass Door):

- A. Fiber-cement board manufactured by James Hardie Building Products or approved equivalent, size to fit new appurtenance and opening.
- B. Cellular Vinyl PVC manufactured by Royal Mouldings Limited or approved equivalent, size to fit new appurtenance and opening.
- C. Concrete: 3,000 psi w/ pea gravel aggregate. Reinforced w/ (2) cont. #4 rebar.

3.4 Waterproofing Membrane (Balcony & Patio Decks):

A. Tiled Surfaces:

1. NEOGARD liquid applied polyurethane waterproofing coating or approved equivalent system.
2. The NEOGARD system shall be used in all areas where tile is anticipated to be reinstalled – tile must be reinstalled within 60 days following application. Broadcast silica sand in wet NEOGARD for tile adhesion.

B. Exposed Surfaces:

1. NEOGARD Peda-Gard liquid applied polyurethane waterproofing coating system. Current balcony silica sand color and texture shall match.

C. Accessories:

1. Primer: NEOGARD approved primers.
2. Aggregate: colored quartz to match existing; local aggregate approved by coating manufacturer.

3.5 Flashing Membrane:

A. Type: Prosoco R-Guard FastFlash or approved equivalent.

B. Related Materials: Provide primer, mastic, sealant and other miscellaneous products as required by the manufacturer to be compatible with specified waterproofing membrane.

3.6 Joint Sealants:

A. Sealant:

1. Exposed Sealants: MasterSeal NP 10 or accepted alternate manufactured by BASF Construction Chemicals, LLC-Building Systems or approved equivalent.
2. Sealants Incorporated into deck coating: Sikaflex 15 LM, manufactured by Sika Corporation.

B. Joint Backing: Round, closed-cell, polyethylene foam rod compatible with sealant; oversized 30 to 50 percent larger than joint width.

C. Bond Breaker Tape: Adhesive backed polyethylene tape with slick-surfaced facing by Pecora or approved equivalent. Width sized to suit joint.

3.7 Fasteners: Doorframes shall be installed using 300 Series stainless steel screws.

PART 4 – EXECUTION

4.1 General:

- A. All work shall be coordinated with the unit Owner, the Owner's representative, the Association Board and with the appropriate management firm and/or association representative for notification of work to begin and scheduling of inspections.
- B. Contractor shall post appropriate permit documents on site.

4.2 Removal:

- A. Remove existing fenestration from opening, taking care not to damage finishes.
- B. Legally dispose of removed fenestration.
- C. All exterior trim, existing caulk, flashing, etc. shall be removed.
- D. Remove all miscellaneous materials, fasteners, sealants, etc. Clean all surfaces to produce a smooth finish.
- E. Remove exterior finish and accessories, wood blocking, drywall, interior trim, etc. as required to install new window or sliding glass door.
- F. Prior to cutting stucco or drywall, contractor shall mark work using straight and true cut lines.
- G. Cuts shall not be made into the exterior sheathing or wall framing.
- H. If damaged framing or sheathing is encountered, finishes shall be removed as required to expose the extent of the damage and as necessary to permit its repair.

4.3 Examination:

- A. Contractor shall request a field review involving the Engineer and a Representative of the Association Board or Owner's Representative to assess the condition of the opening where assemblies have been removed. All parties present shall conduct an examination of the existing conditions to document any deteriorated or damaged wall framing, stucco, drywall or miscellaneous work needing repair.
- B. Contractor shall identify, in writing, conditions that will prevent proceeding with the work. If the Contractor fails to document the adverse conditions and/or proceeds with work without repairing unsatisfactory conditions, the sole responsibility shall be that of the Contractor.

4.4 Installation of New Door Units:

- A. Storage and Handling: All new door assemblies shall be stored and transported in such a manner to prevent scratching, deformation, or racking of the frames. It is the right of the owner or the owner's representative to require replacement of any units containing such damage.
- B. Contractor shall verify that new door units are sized to fit existing rough openings.
- C. Sill pans shall be installed as shown on the replacement details.
- D. If fasteners must be installed through the sill pan, they must be installed in a predrilled hole, injected with sealant. The installed fastener head must also be capped with sealant.
- E. New door units shall be installed in accordance with the manufacturer's installation instructions, ASTM E 2112 and in accordance with the replacement details.
- F. Install door unit on a curb (in-organic material) that provides a 1-1/2" minimum step up from exterior finish floor surface. Secure curb with 1/4" diameter stainless steel concrete screws with minimum 2" embedment into concrete substrate at 6" on center, staggered.
- G. Set door units plumb, level, and true to line, without warp or rack of frames or sash. Provide proper support and anchor securely in place.
- H. Separate aluminum and other corrodible surfaces from sources of corrosion or electrolytic action at points of contact with other materials by complying with the requirements specified under paragraph "Dissimilar Materials" in the Appendix to AAMA 101.

4.5 Waterproofing Membrane (For Door Curb Installation):

- A. Preparation:
 - 1. Contractor shall remove any tile, paver, or other floor finishes from a 12-inch wide area of the balcony floor adjacent to the door opening to expose the existing waterproof deck coating. Care shall be taken not to damage the existing waterproofing membrane surface, if present.
 - 2. Contractor shall ensure that the existing waterproofing membrane is compatible with the new waterproofing membrane system. Contractor shall coordinate with the manufacturer to test the surface for adherence, to ensure compatibility.
 - 3. Clean all deck surfaces to receive coating system in accordance with manufacturer's instructions; vacuum clean or blow clean with oil-free compressed air all surfaces to receive sealants, detailing materials or coatings immediately prior to installation.
 - 4. Rout, clean, prepare and detail surface cracks in accordance with manufacturer's instructions; install backer rod where required.
 - 5. Clean metal surfaces to bright metal by wire brushing or mechanical etching; scuff-sand lead flashing and plastic surfaces.

6. Prime surfaces in accordance with manufacturer's instructions.
7. Install properly sized diameter backer rod or bond breaker tape into corner of all 90-degree junctures and cover with 1" detail cant of approved sealant.
8. Allow detail applications to cure in accordance with manufacturer's instructions, prior to general application of coating.
9. Surface preparation, detailing and tie-in procedures shall be in accordance with waterproof coating system manufacturer's instructions.

B. Application:

1. Verify proper dry condition of substrate using method recommended by coating system manufacturer; perform adhesion checks prior to general application of coating system using field adhesion test method recommended by manufacturer.
2. Mask off adjoining surfaces not to receive coating system.
3. DO NOT APPLY waterproofing coating system over PRESSURE TREATED LUMBER.
4. Select Appropriate NOEGARD waterproof membrane system based on existing and intended conditions.
5. Install waterproof coating system in accordance with manufacturer's recommendations and instructions. Lap new material over existing membrane, if present a minimum of 4-inches.
6. Grid deck surfaces to assure proper coverage rates and verify coating wet-film mil thickness with gauges as work progresses.
7. Apply base coat uniformly and allow to cure in accordance with manufacturer's instructions.
8. Wipe clean all detail coats with white rags wetted with Xylene solvent; do not saturate detail coat.
9. Clean area minimum 6" wide along terminating edge of existing coating with Xylene solvent on clean white rags prior to of new coating. Use interlaminar primer per manufacturer's instructions, as needed.
10. For tile installations, immediately broadcast aggregate into wet material to refusal. Loose aggregate must be removed before tile installation, if applicable.
11. Allow membrane to cure per manufacturer's instructions.
12. Where waterproofing membrane does not exist, the new waterproofing membrane that is installed under the door sill pan shall extend onto the balcony deck or patio for the full width of the removed floor finish.

4.6 Flashing Membrane:

- A. Membranes shall be installed according to manufacturer's installation instructions and as shown on replacement details.
- B. Prime surfaces as recommended by manufacturer.

4.7 Clean-Up

- A. Contractor shall remove all unused materials from the project site.

- B. All surfaces shall be swept clean daily.
- C. Contractor shall final clean all replacement window and sliding glass door units per manufacturer's instructions.

END OF SECTION

SECTION 081000 - EXTERIOR SWING DOOR REPLACEMENT

PART 1 – GENERAL

1.1 Scope of Work:

- A. Removal of existing doors and associated exterior and interior trim where required. Existing Hurricane Shutters and associated accessories shall be removed by owner prior to replacement.
- B. Removal of existing exterior stucco and interior drywall as required.
- C. Replacement of existing doors including installation of all flashing, waterproofing, stucco, accessories and caulk/sealants as required to produce a complete watertight installation.
- D. Removal and replacement of deteriorated wall framing, exterior sheathing and wall insulation when encountered at openings. Contact EOR for further direction.

1.2 Permits, Fees and Insurance:

- A. The Owner and/or their contractor shall coordinate all approvals through the Association Board.
- B. Contractor shall secure all necessary permits prior to commencement of the work.
- C. Contractor shall procure and maintain in force until the completion of work the following insurances in the amounts required by the Owner and the Association Board: general liability insurance, employer's liability insurance, automobile insurance and worker compensation. Contractor shall insure that current insurance certificates are on file with owner and with the appropriate management firm and/or association representative.

1.3 Quality Assurance:

- A. Comply with governing codes and regulations. Provide products of acceptable manufacturers, approved by the local building code agency and have been in satisfactory use in similar service for three years. Use experienced installers.
- B. It is the responsibility of the Contractor to ensure that the replacement door unit's design wind pressures, at the time of procurement and installation, comply with the current Florida Building Code. CONTRACTOR SHALL CONTACT ENGINEER TO VERIFY COMPLIANCE.
- C. Manufacturer's Qualifications: Company specializing in the manufacture of products for a minimum of 5 years. Company shall be a member of the American Architectural Manufacturers Association (AAMA).

- D. Installer Qualifications: Company specializing in the performance of the work for a minimum of 5 years.
- E. All work shall be performed in accordance with the manufacturer's recommended installation instructions and details.
- F. Contractor may substitute other equivalent products as approved by the Owner and Association Board.
- G. All temporary utility services, including toilet facilities, are to be obtained and paid for by the contractors performing the work described herein.
- H. Contractor shall perform a mockup of the complete door installation prior to production work to confirm the constructability, performance, and aesthetic appearance of the work satisfies the owner and engineer's criteria.

1.4 Warranty

- A. Manufacturer: Provide manufacturer's standard warranty.
- B. Installer: Provide all labor and materials required to repair work that fails to perform for (5) five years following the date of substantial completion.

1.5 System Performance Requirements:

- A. General: Provide vinyl door units that comply with performance requirements specified, as demonstrated by testing the manufacturer's corresponding stock systems. Door manufacturer to have tested proposed assembly units through a recognized independent testing laboratory or agency using the tests & test procedures specified below, and in accordance with procedures specified in AAMA 101, including requirements of AAMA 101, Section 3, "Optional Performance Classes." All assemblies shall be in accordance with the current Building Code.
- B. Design Pressure Requirements (Components and Cladding): -70/+70 psf.
- C. Uniform Load Structural and Deflection Tests: Test in accordance with ASTM E 330 at 150 percent of the design pressure. After each specified loading there shall be no glass breakage, permanent damage to fasteners, hardware parts, support arms or actuating mechanisms or any other damage which causes the door to be inoperable. No member shall deflect more than 1/175 of its span under load, and there shall be no permanent deformation of any main frame, sash, pane, or ventilator member in excess of 0.2 percent of its span.
- D. Water Penetration: Test in accordance with ASTM E331, at 11 psf and ASTM E 547 at 11 psf. There shall be no water penetration as defined in the test method. The AMMA permitted 1/3 reduction in passing criteria for testing of field installations shall NOT be allowed.

- E. Impact Resistance: Provide door units and glazing that have been tested to pass the large and small missile impact test per ASTM E 1886. Obtain prior permission from Owner if non-impact glass is intended to be used.
- F. Air infiltration: Test in accordance with ASTM E 283 at 6.24 lbf/ft². Air infiltration rate shall not exceed 0.03 cfm/ft².
- G. Forced-Entry Resistance: Provide door units that comply with requirements for Performance Level 10 when tested in accordance with AAMA 1302.5-76 Test A through G.
- H. Condensation Resistance Factor (CRF): Provide doors with a minimum CRF of 62 per AAMA 1503.
- I. Energy Performance: Provide door units with a maximum thermal transmittance (u-value) of 0.40 (to achieve an Energy Star Rating) when tested in accordance with AAMA 1503.1, latest edition.
- J. Solar Heat Gain Coefficient (SHGC): Provide doors with SHGC <0.25 (to achieve an Energy Star Rating).
- K. Light emission: Provide door units with inside-to-outside visible light transmittance (VLT) value of 45% or less to comply with Florida Statute 161.163 and Florida Administrative Code Rule 62B-55 or other local ordinance requirements for light emission for the protection of sea turtle nesting when required.

1.6 Work Performance Field Verification:

- A. Watertight performance of all work is required.
- B. All newly installed doors may be subjected to a visual inspection, operation test, an AAMA 501.2 hose test (for fixed windows), and an AAMA 502 Sill Dam Test following completed installation and prior to the installation of interior trim components.
- C. At the owner's option, installed assemblies may be tested in accordance with ASTM E 1105 at 15% of the structural design pressure rating. There shall be no water penetration as defined in the test method. The AMMA permitted 1/3 reduction in passing criteria for testing of field installations shall NOT be allowed for new installations.
- D. New doors that do not pass water testing shall be repaired or replaced per the Owner's Representative's discretion.

PART 2 - SUBMITTALS

2.1 General:

- A. Contractor shall submit proof of employer's liability insurance, general liability insurance, automobile insurance and workman's compensation.
- B. Contractor shall submit names and addresses for all suppliers and all subcontractors providing materials and/or labor on project.
- C. For substitutions, Contractor shall submit proof data to demonstrate that substitutions are equal in performance and durability to materials specified.
- D. Contractor shall submit 4 copies of all requested submittal materials to the Association Board for approval prior to commencement of the work. Contractor shall indicate Owner's approval on submittal cover sheet.

2.2 Door Units:

- A. Product Data: Contractor shall submit manufacturer's product literature for all products and accessories furnished.
- B. Florida Building Code approval and/or Miami-Dade Notice of Acceptance "NOA" indicating the specific model/series product's compliance with code requirements.
- C. Design Pressure Calculation for each window or door opening to be modified.
- D. Installation Instructions: Contractor shall submit manufacturer's installation instruction sheets for all products and accessories furnished.
- E. Contract Closeout Submittals: Contractor shall submit to the owner bound manual clearly identified with project name, location and completion date. Identify type and size of new window and sliding glass door units installed. Provide recommendations for periodic inspections, care and maintenance.

2.3 Contractor shall provide manufacturer's product literature, installation instructions and color samples (exposed materials only) for the following:

- A. Fluid-applied membrane flashing and/or waterproofing
- B. Self-adhered membrane flashing and/or waterproofing
- C. Joint sealant & backing materials

PART 3 - MATERIALS

3.1 Door Units:

- A. Hardware: Stainless steel or approved equivalent corrosion resistant material for the salt air environment.

- B. Color: to match existing.
- C. Swing Doors: WinDoor Hinged Outswing Aluminum (equal leg, no fin). Model 9050 Series or accepted alternate. Florida Product Approval Number 331.2.

3.2 Sill Flashing:

- A. Sill Flashing:
 - 1. Type:
 - a. AISI type 316 stainless steel complying with ASTM A-167, with 2D annealed finish. Minimum thickness to be 0.0156" (28 gauge) U.O.N. All corner joints shall be welded.
 - b. PVC manufactured by Jamsill Guard or approved equivalent, size to fit new appurtenance and opening.
 - 2. Dimensions:
 - a. Vertical: Back and end legs compliant with height requirements of Table A3.1 of ASTM E 2112.
 - b. Horizontal: width of pan shall fit the full width of the rough opening so that the base of the vertical perimeter sealant joints are captured within the pan.
 - c. Lateral: Sill pan tray and end dams shall project beyond the exterior plane of the window frame or door frame. The leading horizontal edge of the tray shall contain a down turned leg of a minimum of 3/8-inch.
 - d. End Dam Terminations: Shall project beyond the jamb's perimeter sealant joint. Where exposed to the exterior, the pan legs shall be hemmed and curve cut.
 - 3. Slope: the pan shall be sloped a minimum of 1/8":6" toward the exterior by means necessary.
 - 4. Joints: Fully fused by soldering, welding, or PVC liquid cement. Caulk shall not be used to seal PVC pan overlaps PVC liquid cement must be used.
 - 5. Sealing:
 - a. Installation: Pan shall be set in (3) parallel generously applied continuous beads of sealant along its length and at the corners of the rough opening.
 - b. Interior: The top legs (back and ends) of the sill pan shall be continuously sealed to the doorframe to prevent passage of air from outside to inside.
 - c. Exterior: The underside of the pan and the outside surface of the end dams shall be sealed to the wall.
 - 6. Flashing material: Prosoco R-Guard FastFlash or approved equivalent.

3.3 Flashing Membrane:

- A. Type: Prosoco R-Guard FastFlash or approved equivalent.
- B. Related Materials: Provide primer, mastic, sealant and other miscellaneous products as required by the manufacturer to be compatible with specified waterproofing membrane.
- C. Membrane shall be installed according to manufacturer's installation instructions.

D. Prime surfaces as recommended by manufacturer.

3.4 Joint Sealants:

A. Sealant:

1. Exposed Sealants: Sonolastic 150 manufactured by BASF Construction Chemicals, LLC-Building Systems or approved equivalent.
2. Sealants Incorporated into deck coating: Sonolastic NP1 by BASF Construction Chemicals, LLC-Building Systems or approved equivalent.

B. Joint Backing: Round, closed-cell, polyethylene foam rod compatible with sealant; oversized 30 to 50 percent larger than joint width.

C. Bond Breaker Tape: Adhesive backed polyethylene tape with slick-surfaced facing by Pecora or approved equivalent. Width sized to suit joint.

3.5 Fasteners: Doorframes shall be installed using 300 Series stainless steel screws.

PART 4 – EXECUTION

4.1 General:

- A. All work shall be coordinated with the unit Owner, the Owner's representative, the Association Board and with the appropriate management firm and/or association representative for notification of work to begin and scheduling of inspections.
- B. Contractor shall post appropriate permit documents on site.

4.2 Removal:

- A. Remove existing fenestration from opening, taking care not to damage finishes.
- B. Legally dispose of removed fenestration.
- C. All exterior trim, existing caulk, flashing, etc. at perimeter shall be removed.
- D. Remove all miscellaneous materials, fasteners, sealants, etc. Clean all surfaces to produce a smooth finish.
- E. Remove exterior finish and accessories, wood blocking, drywall, interior trim, etc. as required to install new door.
- F. Prior to cutting stucco/EIFS or drywall, contractor shall mark work using straight and true cut lines.

- G. Cuts shall not be made into the exterior sheathing or wall framing without prior approval.
- H. If damaged framing or sheathing is encountered, finishes shall be removed as required to expose the extent of the damage and as necessary for proper repair.

4.3 Examination:

- A. Contractor shall request a field review involving the Engineer and a Representative of the Association Board to assess the condition of the opening where assemblies have been removed. All parties present shall conduct an examination of the existing conditions to document any deteriorated or damaged wall framing, stucco, drywall or miscellaneous work needing repair.
- B. Contractor shall identify, in writing, conditions that will prevent proceeding with the work. If the Contractor fails to document the adverse conditions and/or proceeds with work without repairing unsatisfactory conditions, the sole responsibility shall be that of the Contractor.

4.4 Installation of New Doors:

- A. Contractor shall verify that new door units are sized to fit existing rough openings.
- B. If fasteners must be installed through the sill pan, they must be installed in a predrilled hole, injected with sealant. The installed fastener head must also be capped with sealant.
- C. New door units shall be installed in accordance with the manufacturer's installation instructions and ASTM E 2112 and in accordance with the manufacturer's replacement details.
- D. Set door units plumb, level, and true to line, without warp or rack of frames or sash. Provide proper support and anchor securely in place.
- E. Separate aluminum and other corrodible surfaces from sources of corrosion or electrolytic action at points of contact with other materials by complying with the requirements specified under paragraph "Dissimilar Materials" in the Appendix to AAMA 101.

4.5 Storage & Clean-Up

- A. Storage and Handling: All new door assemblies shall be stored and transported in such a manner to prevent scratching, deformation, or racking of the frames. It is the right of the owner or the owner's representative to require replacement of any units containing such damage.
- B. Contractor shall remove all unused materials from the project site.
- C. All surfaces shall be swept clean daily.

- C. Contractor shall final clean all replacement window and sliding glass door units per manufacturer's instructions.

END OF SECTION

SECTION 085313 - WINDOW REPLACEMENT

PART 1 – GENERAL

1.1 SCOPE OF WORK:

- A. Removal of existing windows and associated exterior and interior trim and drywall where required. Existing Hurricane Shutters and associated accessories shall be removed by owner prior to replacement.
- B. Removal of existing exterior stucco/EIFS and interior drywall as required.
- C. Replacement of existing windows including installation of all flashing, waterproofing, stucco/EIFS, accessories and caulk/sealants as required to provide a complete watertight installation.
- D. Removal and replacement of deteriorated wall framing, exterior sheathing and wall insulation when encountered at openings. Contact EOR for further direction.

1.2 PERMITS, FEES AND INSURANCE:

- A. The Owner and/or their contractor shall coordinate all approvals through the Association Board and the Architectural Review Board, as applicable.
- B. Contractor shall secure all necessary permits prior to commencement of the work.
- C. Contractor shall procure and maintain in force until the completion of work the following insurances in the amounts required by the Owner and the Association Board: general liability insurance, employer's liability insurance, automobile insurance and worker compensation. Contractor shall insure that current insurance certificates are on file with the owner and with the appropriate management firm and/or association representative.

1.3 QUALITY ASSURANCE:

- A. Comply with governing codes and regulations. Provide products of acceptable manufacturers, approved by the local building code agency and have been in satisfactory use in similar service for three years. Use experienced installers.
- B. It is the responsibility of the Contractor to ensure that the replacement door units design wind pressures, at the time of procurement and installation, comply with the current Florida Building Code. CONTRACTOR SHALL CONTACT ENGINEER TO VERIFY COMPLIANCE.

- C. Manufacturer's Qualifications: Company specializing in the manufacture of products for a minimum of 5 years. Company shall be a member of the American Architectural Manufacturers Association (AAMA).
- D. Installer Qualifications: Company specializing in the performance of the work for a minimum of 5 years. Company shall be a member of the American Architectural Manufacturers Association (AAMA).
- E. All work shall be performed in accordance with the manufacturer's recommended installation instructions and details.
- F. Contractor may substitute other equivalent products as approved by the Owner and Association Board.
- G. All temporary utility services, including toilet facilities, are to be obtained and paid for by the contractors performing the work described herein.
- H. Contractor shall perform a mockup of the complete window installation prior to production work to confirm the constructability, performance, and aesthetic appearance of the work satisfies the owner and engineer's criteria.

1.4 WARRANTY:

- A. Manufacture: Provide manufacturer's standard warranty.
- B. Installer: Provide all labor and materials required to repair work that fails to perform for five (5) years following the date of substantial completion.

1.5 SYSTEM PERFORMANCE REQUIREMENTS:

- A. General: Provide vinyl window units that comply with performance requirements specified, as demonstrated by testing the manufacturer's corresponding stock systems. Window manufacturer to have tested proposed assembly units through a recognized independent testing laboratory or agency using the tests & test procedures specified below, and in accordance with procedures specified in AAMA 101, including requirements of AAMA 101, Section 3, "Optional Performance Classes." All assemblies shall be in accordance with the current Building Code.
- B. Design Pressure Requirements (Components and Cladding): -70/+70 psf.
- C. Uniform Load Structural and Deflection Tests: Test in accordance with ASTM E 330 at 150 percent of the design pressure. After each specified loading there shall be no glass breakage, permanent damage to fasteners, hardware parts, support arms or actuating mechanisms or any other damage which causes the window to be inoperable. No member shall deflect more than 1/175 of its span under load, and there shall be no permanent deformation of any main frame, sash, pane, or ventilator member in excess of 0.2 percent of its span.

- D. Water Penetration: Test in accordance with ASTM E331, at 11 psf and ASTM E 547 at 11 psf. There shall be no water penetration as defined in the test method. The AMMA permitted 1/3 reduction in passing criteria for testing of field installations shall NOT be allowed.
- E. Impact Resistance: Provide window units and glazing that have been tested to pass the large and small missile impact test per ASTM E 1886. Obtain prior permission from Owner if non-impact glass is intended to be used.
- F. Air infiltration: Test in accordance with ASTM E 283 at 6.24 lbf/ft². Air infiltration rate shall not exceed 0.03 cfm/ft².
- G. Forced-Entry Resistance: Provide windows units that comply with requirements for Performance Level 10 when tested in accordance with AAMA 1302.5-76 Test A through G.
- H. Condensation Resistance Factor (CRF): Provide windows with a minimum CRF of 62 per AAMA 1503.
- I. Energy Performance: Provide windows units with a maximum thermal transmittance (u-value) of 0.40 (to achieve an Energy Star Rating) when tested in accordance with AAMA 1503.1, latest edition.
- J. Solar Heat Gain Coefficient (SHGC): Provide windows with SHGC <0.25 (to achieve an Energy Star Rating).
- K. Light emission: Provide window units with inside-to-outside visible light transmittance (VLT) value of 45% or less to comply with Florida Statute 161.163 and Florida Administrative Code Rule 62B-55 or other local ordinance requirements for light emission for the protection of sea turtle nesting when required.

1.6 WORK PERFORMANCE FIELD VERIFICATION:

- A. Watertight performance of all work is required.
- B. All newly installed windows may be subjected to a visual inspection, operation test, an AAMA 501.2 hose test (for fixed windows), and an AAMA 502 Sill Dam Test following completed installation and prior to the installation of interior trim components.
- C. At the owner's option, installed assemblies may be tested in accordance with ASTM E 1105 at 15% of the structural design pressure rating. There shall be no water penetration as defined in the test method. The AMMA permitted 1/3 reduction in passing criteria for testing of field installations shall NOT be allowed for new installations.

- D. New windows that do not pass water testing shall be repaired or replaced per the Owner's Representative's discretion.

PART 2 - SUBMITTALS

2.1 GENERAL:

- A. Contractor shall submit proof of employer's liability insurance, general liability insurance, automobile insurance and workman's compensation.
- B. Contractor shall submit names and addresses for all suppliers and all subcontractors providing materials and/or labor on project.
- C. For substitutions, Contractor shall submit proof data to demonstrate that substitutions are equal in performance and durability to materials specified. Data shall include but not be limited to Florida Building Code Approval, Miami Dade NOA, and complete installation instructions.
- D. Contractor shall submit 3 copies of all requested submittal materials to the Association Board for approval prior to commencement of the work. Contractor shall indicate Owner's approval on submittal cover sheet.

2.2 WINDOWS:

- A. Product Data: Contractor shall submit manufacturer's product literature for all products and accessories furnished.
- B. Installation Instructions: Contractor shall submit manufacturer's installation instruction sheets for all products and accessories furnished.
- C. Contract Closeout Submittals: Contractor shall submit to the owner bound manual clearly identified with project name, location and completion date. Identify type and size of new windows installed. Provide recommendations for periodic inspections, care and maintenance.

2.3 Contractor shall provide manufacturer's product literature, installation instructions and color samples (exposed materials only) for the following:

- A. Waterproofing membrane
- B. Joint sealant & backing materials
- C. Elastomeric coating materials
- D. Metal flashing materials

PART 3 - MATERIALS

3.1 WINDOWS:

- A. Manufacturer: WinDoor or approved equivalent
- B. Model, Replacement Windows Fixed Transom: Windoor 3000 Series or accepted alternate. Provide Florida Product Approval Number
- C. Frame: Match existing window profile (equal leg, no fin).
- D. Style: Match appearance of the existing.
- E. Glass: Double pane insulated clear glass, or as directed by association.
- F. Hardware: As selected by the association. All components shall be stainless steel or equivalent corrosion resistance.
- G. Color: To match existing assemblies.
- H. Coating: Suitable for aggressive chloride rich environment.

3.1 FLASHING MEMBRANE:

- A. Type: Prosoco R-Guard FastFlash or approved equivalent.
- B. Related Materials: Provide primer, mastic, sealant and other miscellaneous products as required by the manufacturer to be compatible with specified waterproofing membrane.
- C. Membrane shall be installed according to manufacturer's installation instructions.
- D. Prime surfaces as recommended by manufacturer.

3.2 JOINT SEALANTS:

- A. Sealants:
 - a. Metal to EIFS: Dow 795 or approved Silicone equivalent.
 - b. Metal to Metal: Dow 795 or approved Silicone equivalent
 - c. Prosoco R-Guard FastFlash
- B. Backing Materials
 - a. Backer Rod: Round, closed-cell, polyethylene foam rod compatible with sealant; oversized 30 to 50 percent larger than joint width.
 - b. Bond Breaker Tape: Adhesive backed polyethylene tape with slick-surfaced facing by Pecora or approved equivalent. Width sized to suit joint.
- C. Primer:
 - a. As required by the manufacture to achieve bond to substrate.

- D. Profile:
 - a. Adhesive face and profile compliant with Dow Installation Handbook: 3/8" minimum adhesive face.

3.3 Fasteners: All components shall be installed using Series 300 stainless steel screws and anchors.

PART 4 – EXECUTION

4.1 GENERAL:

- A. All work shall be coordinated with the unit Owner, the Owner's representative, the Association Board and with the appropriate management firm and/or association representative for notification of work to begin and scheduling of inspections.
- B. Contractor shall post appropriate permit documents on site

4.2 REMOVAL:

- A. Remove existing fenestration from opening, taking care not to damage finishes.
- B. Legally dispose of removed fenestration.
- C. All exterior trim, existing caulk, flashing, etc. at perimeter shall be removed.
- D. Remove all miscellaneous materials, fasteners, sealants, etc. Clean all surfaces to produce a smooth finish.
- E. Remove exterior finish and accessories, wood blocking, drywall, interior trim, etc. as required to install new window.
- F. Prior to cutting stucco/EIFS or drywall, contractor shall mark work using straight and true cut lines.
- G. Cuts shall not be made into the exterior sheathing or wall framing without prior approval.
- H. If damaged framing or sheathing is encountered, finishes shall be removed as required to expose the extent of the damage and as necessary for proper repair.

4.3 EXAMINATION:

- A. Contractor shall request a field review involving the Contractor and a representative of the Association Board or Owners Representative to assess the condition of the opening where the window has been removed. All parties present shall conduct an examination

of the existing conditions documenting any deteriorated or damaged wall framing, stucco, drywall or miscellaneous work needing repair.

- B. Contractor shall identify, in writing, conditions that will prevent proceeding with the work. If the Contractor fails to document the adverse conditions and/or proceeds with work without repairing unsatisfactory conditions, the sole responsibility for any and all replacement or repair work shall be that of the Contractor.


4.4 INSTALLATION OF NEW WINDOWS:

- A. Contractor to verify that new windows are sized to match existing windows.
- B. New windows shall be installed in accordance with applicable portions of ASTM E 2112, the manufacturer's installation instructions, provided details, and project documents.
- C. Set window units plumb, level, and true to line, without warp or rack of frames or sash. Provide proper support and anchor securely in place.
- D. Flashings and sealants shall be installed as shown in the details of the project documents, as specified above, and in strict accordance with the manufacturer's installation instructions.
- E. Separate aluminum and other corrodible surfaces from sources of corrosion or electrolytic action at points of contact with other materials by complying with the requirements specified under paragraph "Dissimilar Materials" in the Appendix to AAMA 101.
- F. Where damaged, install EIFS in accordance with EIMA requirements and coat with same coating type and color currently applied per the manufacturer's instructions. If color does not match, entire peripheral area shall be coated to the next wall interruption.
- G. Interior finishes, where damaged or affected by window installation shall be repaired or replaced to match the existing appearance.

4.5 STORAGE AND CLEAN-UP

- A. All new window assemblies shall be stored and transported in such a manner to prevent scratching, deformation, or racking of the frames. It is the right of the owner or the owner's representative to require replacement of any units containing such damage.
- B. Contractor shall remove all removed and unused materials from the project site.
- C. All surfaces shall be swept clean daily.
- D. Contractor shall final clean all replacement windows per manufacturer's instructions.

END OF SECTION



Notes:

1. Existing EIFS, do not damage.
2. Apply flashing membrane over sill of window rough opening extending onto surface of existing aluminum flashing.
3. Sill pan to be set in full bed of sealant. Seal all penetrations through sill pan.
4. Sill pan to have integral rear & end dams – refer to Detail 5. Height of rear and end dams to match window design.
5. Set window in full bed of sealant inside of sill pan and seal end dams to inside flange of window frame.
6. All existing window components, sealants, waterproofing materials, etc. in window rough opening shall be removed in their entirety prior to installation of new window.
7. If window manufacturer requires fastening through the sill pan, fasteners shall be into predrilled holes filled with sealant and capped with sealant.
8. Drawings shall be used in conjunction with specification Section 08 53 13. Drawings cannot be used exclusively.
9. EIFS to receive new sealant shall have existing textured finish coat removed from surface of base coat in accordance with EIFS manufacturer's recommendations. Sealant shall be applied to base coat only.
10. Attachments shall be per Florida Building Code Product Approval Documentation.

2A-1

Replacement Window Sill
NTS

Please note that this detail is applicable at the time of its issuance and should not be relied upon at substantially later dates.

This drawing document is the property of Construction Solutions, Inc. Any use or reproduction of this document without the expressed written consent of Construction Solutions, Inc. is prohibited. All rights of design and invention are expressly reserved.



CONSTRUCTION SOLUTIONS, INC.
ENGINEERING · TESTING ·
PROJECT MANAGEMENT

961687 GATEWAY BLVD, SUITE 101C
AMELIA ISLAND, FLORIDA 32034

CERTIFICATE OF AUTHORIZATION NO. 26752


Detail 2A-1 : Window Sill
Beach Walker Villas Condominiums
Amelia Island, Florida

Date: 5/21/20

Scale: N.T.S.

Drawn: RMR

Sheet: 1 of 9



Notes:

1. Apply flashing membrane over sill of window rough opening extending onto surface of existing roof.
2. Install new inorganic curb with minimum 1-1/2" step up from exterior finish floor surface. Set in full bed of sealant. Secure with 1/4" stainless steel Tapcons with minimum 2" embedment into concrete at 6" on center, staggered.
3. Pan flashing and sill pan to have integral rear & end dams – refer to Detail 5. Height of rear and end dams to match window design.
4. Pan flashing and sill pan to be set in full bed of sealant. Seal all penetrations through pans.
5. Set window in full bed of sealant inside of sill pan and seal end dams to inside flange of window frame.
6. All existing window components, sealants, waterproofing materials, etc. in window rough opening shall be removed in their entirety prior to installation of new window.
7. If window manufacturer requires fastening through the sill pan, fasteners shall be into predrilled holes filled with sealant and capped with sealant.
8. Drawings shall be used in conjunction with specification Section 08 53 13. Drawings cannot be used exclusively.
9. EIFS to receive new sealant shall have existing textured finish coat removed from surface of base coat in accordance with EIFS manufacturer's recommendations. Sealant shall be applied to base coat only.
10. Attachments shall be per Florida Building Code Product Approval Documentation.

2A-2

Replacement Window Sill at Low Roof NTS

Please note that this detail is applicable at the time of its issuance and should not be relied upon at substantially later dates.

This drawing document is the property of Construction Solutions, Inc. Any use or reproduction of this document without the expressed written consent of Construction Solutions, Inc. is prohibited. All rights of design and invention are expressly reserved.



CONSTRUCTION SOLUTIONS, INC.
ENGINEERING · TESTING ·
PROJECT MANAGEMENT

961687 GATEWAY BLVD, SUITE 101C
AMELIA ISLAND, FLORIDA 32034

CERTIFICATE OF AUTHORIZATION NO. 26752


Detail 2A-2 : Window Sill at Low Roof
Beach Walker Villas Condominiums
Amelia Island, Florida

Date: 5/21/20

Scale: N.T.S.

Drawn: RMR

Sheet: 2 of 9



Notes:

1. Existing EIFS, do not damage.
2. Apply flashing membrane over jamb of window rough opening extending onto edge of EIFS.
3. Shingle flashing membrane over sill pan end dams.
4. All existing window components, sealants, waterproofing materials, etc. in window rough opening shall be removed in their entirety prior to installation of new door.
5. Drawings shall be used in conjunction with specification Sections 08 53 13. Drawings cannot be used exclusively.
6. EIFS to receive new sealant shall have existing textured finish coat removed from surface of base coat in accordance with EIFS manufacturer's recommendations. Sealant shall be applied to base coat only.
7. Attachments shall be per Florida Building Code Product Approval Documentation.

2B

Replacement Window Jamb
NTS

Please note that this detail is applicable at the time of its issuance and should not be relied upon at substantially later dates.

This drawing document is the property of Construction Solutions, Inc. Any use or reproduction of this document without the expressed written consent of Construction Solutions, Inc. is prohibited. All rights of design and invention are expressly reserved.



CONSTRUCTION SOLUTIONS, INC.
ENGINEERING · TESTING ·
PROJECT MANAGEMENT

961687 GATEWAY BLVD, SUITE 101C
AMELIA ISLAND, FLORIDA 32034

CERTIFICATE OF AUTHORIZATION NO. 26752


Detail 2B: Window Jamb
Beach Walker Villas Condominiums
Amelia Island, Florida

Date: 5/21/20

Scale: N.T.S.

Drawn: RMR

Sheet: 3 of 9



Notes:

1. Existing EIFS, do not damage.
2. Apply flashing membrane over existing concrete at head of window rough opening extending onto edge of EIFS.
3. All existing window components, sealants, waterproofing materials, etc. in window rough opening shall be removed in their entirety prior to installation of new door.
4. Drawings shall be used in conjunction with specification Sections 08 53 13. Drawings cannot be used exclusively.
5. EIFS to receive new sealant shall have existing textured finish coat removed from surface of base coat in accordance with EIFS manufacturer's recommendations. Sealant shall be applied to base coat only.
6. Attachments shall be per Florida Building Code Product Approval Documentation.

2C

Replacement Window Head
NTS

Please note that this detail is applicable at the time of its issuance and should not be relied upon at substantially later dates.

This drawing document is the property of Construction Solutions, Inc. Any use or reproduction of this document without the expressed written consent of Construction Solutions, Inc. is prohibited. All rights of design and invention are expressly reserved.



CONSTRUCTION SOLUTIONS, INC.
ENGINEERING · TESTING ·
PROJECT MANAGEMENT

961687 GATEWAY BLVD, SUITE 101C
AMELIA ISLAND, FLORIDA 32034

CERTIFICATE OF AUTHORIZATION NO. 26752


Detail 2C: Window Head
Beach Walker Villas Condominiums
Amelia Island, Florida

Date: 5/21/20

Scale: N.T.S.

Drawn: RMR

Sheet: 4 of 9



Notes:

1. All existing door components, sealants, waterproofing materials, etc. in door rough opening shall be removed in their entirety prior to installation of new door.
2. Place new liquid applied flashing membrane on exposed existing surface.
3. Install new inorganic curb with minimum 1-1/2" step up from exterior finish floor surface. Set in full bed of sealant. Secure with 1/4" stainless steel Tapcons with minimum 2" embedment into concrete at 6" on center, staggered.
4. Sill pan to have integral rear & end dams – refer to Detail 5. Height of rear and end dams to match door design.
5. Sill pan to be set in full bed of sealant. Seal all penetrations through sill pan.
6. Set threshold in full bed of sealant inside of sill pan and seal end dams to inside flange of sliding glass door frame.
7. If door manufacturer requires fastening through the sill pan, fasteners shall be into predrilled holes filled with sealant and capped with sealant.
8. Appropriate sized backer rod or bond breaker tape.
9. Drawings shall be used in conjunction with specification Sections 08 00 00 - Sliding Glass Door Replacement, 08 10 00 - Swing Door Replacement. Drawings cannot be used exclusively.
10. Attachments shall be per Florida Building Code Product Approval Documentation.

4A-1

Replacement Sliding Glass Door or Swing Door Sill. No tile on floor. NTS

Please note that this detail is applicable at the time of its issuance and should not be relied upon at substantially later dates.

This drawing document is the property of Construction Solutions, Inc. Any use or reproduction of this document without the expressed written consent of Construction Solutions, Inc. is prohibited. All rights of design and invention are expressly reserved.



CONSTRUCTION SOLUTIONS, INC.
ENGINEERING · TESTING · PROJECT MANAGEMENT

961687 GATEWAY BLVD, SUITE 101C
AMELIA ISLAND, FLORIDA 32034

CERTIFICATE OF AUTHORIZATION NO. 26752


Detail 4A-1 : Sliding Glass or Swing Door Sill
Beach Walker Villas Condominiums
Amelia Island, Florida

Date: 5/21/20

Scale: N.T.S.

Drawn: RMR

Sheet: 5 of 9



Notes:

1. All existing door components, sealants, waterproofing materials, etc. in door rough opening shall be removed in their entirety prior to installation of new door.
2. Place new liquid applied flashing membrane on exposed existing surface.
3. Install new inorganic curb with minimum 1-1/2" step up from exterior finish floor surface. Set in full bed of sealant. Secure with 1/4" stainless steel Tapcons with minimum 2" embedment into concrete at 6" on center, staggered.
4. Sill pan to have integral rear & end dams – refer to Detail 5. Height of rear and end dams to match door design.
5. Sill pan to be set in full bed of sealant. Seal all penetrations through sill pan.
6. Set threshold in full bed of sealant inside of sill pan and seal end dams to inside flange of sliding glass door frame.
7. If door manufacturer requires fastening through the sill pan, fasteners shall be into predrilled holes filled with sealant and capped with sealant.
8. Appropriate sized backer rod or bond breaker tape.
9. Drawings shall be used in conjunction with specification Sections 08 00 00 - Sliding Glass Door Replacement, 08 10 00 - Swing Door Replacement. Drawings cannot be used exclusively.
10. Attachments shall be per Florida Building Code Product Approval Documentation.

4A-2

Replacement Sliding Glass Door or Swing Door Sill. Floor with tile. NTS

Please note that this detail is applicable at the time of its issuance and should not be relied upon at substantially later dates.

This drawing document is the property of Construction Solutions, Inc. Any use or reproduction of this document without the expressed written consent of Construction Solutions, Inc. is prohibited. All rights of design and invention are expressly reserved.



CONSTRUCTION SOLUTIONS, INC.
ENGINEERING · TESTING · PROJECT MANAGEMENT

961687 GATEWAY BLVD, SUITE 101C
AMELIA ISLAND, FLORIDA 32034

CERTIFICATE OF AUTHORIZATION NO. 26752


Detail 4A-2 : Sliding Glass or Swing Door Sill
Beach Walker Villas Condominiums
Amelia Island, Florida

Date: 5/21/20

Scale: N.T.S.

Drawn: RMR

Sheet: 6 of 9



Notes:

1. Existing EIFS, do not damage.
2. Shingle flashing membrane over sill pan end dams.
3. Apply flashing membrane over jamb of door rough opening extending onto edge of EIFS.
4. All existing door components, sealants, waterproofing materials, etc. in door rough opening shall be removed in their entirety prior to installation of new door.
5. Drawings shall be used in conjunction with specification Sections 08 00 00 - Sliding Door Replacement, 08 10 00 - Swing Door Replacement. Drawings cannot be used exclusively.
6. EIFS to receive new sealant shall have existing textured finish coat removed from surface of base coat in accordance with EIFS manufacturer's recommendations. Sealant shall be applied to base coat only.
7. Attachments shall be per Florida Building Code Product Approval Documentation.

4B

Replacement Sliding Glass Door or Swing Door Jamb
NTS

Please note that this detail is applicable at the time of its issuance and should not be relied upon at substantially later dates.

This drawing document is the property of Construction Solutions, Inc. Any use or reproduction of this document without the expressed written consent of Construction Solutions, Inc. is prohibited. All rights of design and invention are expressly reserved.



CONSTRUCTION SOLUTIONS, INC.
ENGINEERING · TESTING ·
PROJECT MANAGEMENT

961687 GATEWAY BLVD, SUITE 101C
AMELIA ISLAND, FLORIDA 32034

CERTIFICATE OF AUTHORIZATION NO. 26752


Detail 4B: Sliding Glass or Swing Door Jamb
Beach Walker Villas Condominiums
Amelia Island, Florida

Date: 5/21/20

Scale: N.T.S.

Drawn: RMR

Sheet: 7 of 9



Notes:

1. Existing EIFS, do not damage.
2. Apply flashing membrane over head of door rough opening extending onto edge of EIFS.
3. All existing door components, sealants, waterproofing materials, etc. in door rough opening shall be removed in their entirety prior to installation of new door.
4. Drawings shall be used in conjunction with specification Section 08 00 00 - Sliding Door Replacement, 08 10 00 - Swing Door Replacement. Drawings cannot be used exclusively.
5. EIFS to receive new sealant shall have existing textured finish coat removed from surface of base coat in accordance with EIFS manufacturer's recommendations. Sealant shall be applied to base coat only.
6. Attachments shall be per Florida Building Code Product Approval Documentation.

4C

Replacement Sliding Glass Door or Swing Door Head
NTS

Please note that this detail is applicable at the time of its issuance and should not be relied upon at substantially later dates.

This drawing document is the property of Construction Solutions, Inc. Any use or reproduction of this document without the expressed written consent of Construction Solutions, Inc. is prohibited. All rights of design and invention are expressly reserved.



CONSTRUCTION SOLUTIONS, INC.
ENGINEERING · TESTING ·
PROJECT MANAGEMENT

961687 GATEWAY BLVD, SUITE 101C
AMELIA ISLAND, FLORIDA 32034

CERTIFICATE OF AUTHORIZATION NO. 26752


Detail 4C: Sliding Glass or Swing Door Head
Beach Walker Villas Condominiums
Amelia Island, Florida

Date: 5/21/20

Scale: N.T.S.

Drawn: RMR

Sheet: 8 of 9



5

Sill Pan Isometric Detail
NTS

Notes:

1. Apply flashing membrane over rough opening of jambs. Extend onto inside face of sill pan end dams.
2. Sill pan to have integral rear & end dams that have seamed watertight joints. Height of rear & end dams to match the design of the window and/or door, respectively or per specifications.
3. Sill pan to be set in full bed of sealant.
4. If window or door manufacturer requires fastening through the sill pan, fasteners shall be into predrilled holes filled with sealant and capped with sealant.
5. Drawings shall be used in conjunction with specification Sections 08 00 00, 08 10 00, and 08 53 13. Drawings cannot be used exclusively.

Please note that this detail is applicable at the time of its issuance and should not be relied upon at substantially later dates.

This drawing document is the property of Construction Solutions, Inc. Any use or reproduction of this document without the expressed written consent of Construction Solutions, Inc. is prohibited. All rights of design and invention are expressly reserved.



CONSTRUCTION SOLUTIONS, INC.
ENGINEERING · TESTING ·
PROJECT MANAGEMENT

961687 GATEWAY BLVD, SUITE 101C
AMELIA ISLAND, FLORIDA 32034

CERTIFICATE OF AUTHORIZATION NO. 26752

Detail 5 - Sill Pan Isometric
Beach Walker Villas Condominiums
Amelia Island, Florida

Date: 5/21/20

Scale: N.T.S.

Drawn: RMR

Sheet: 9 of 9